

# PLATFORM

MOBILE ELEVATED STAGES

## Quick Guide

Read and Understand Operation Guide  
before Operating Stage

### Stage Setup

- 1 Position stage, chock tires, disconnect tow vehicle.
- 2 Level trailer frame lengthwise using tongue jack. **1**
- 3 Extend four (4) frame-mounted leveling jacks. **2**
- 4 Level stage.
- 5 Set intermediate mid-frame jacks (if equipped)
- 6 Remove travel lock-bars **3** - both stage ends.
- 7 Open rear compartment **4** - rotate timer switch **ON**
- 8 Visually verify area around stage is clear.
- 9 Press and hold master safety button.
- 10 Push **LOWER** deck section button.  
\*TIP - Deck may need push from inside to start
- 11 Stop lowering deck slightly above horizontal
- 12 Remove pins from deck truss jacks. **5**
- 13 Lower deck section to horizontal.
- 14 Reinstall deck truss jack pins.
- 15 Adjust truss jack screw feet to level deck.
- 16 Repeat steps to lower and level opposite deck.
- 17 Attach and secure stairs. **6**
- 18 Rotate timer switch **OFF**. **4**
- 19 Stow control pendant and secure compartment.



### Stage Closing

- 1 Remove all accessories attached to deck.
- 2 Open compartment, **4** rotate timer switch **ON**, remove control pendant.
- 3 Verify that stage is clear of obstacles and people.
- 4 Press and hold master safety button.
- 5 Push **RAISE** deck section button until vertical.
- 6 Repeat raise steps for opposite deck section.
- 7 Install front and rear travel lock-bars. **3**
- 8 Extend tongue jack to ground surface. **1**
- 9 If installed - retract mid-frame leveling jacks.
- 10 Retract remaining frame mounted jacks. **2**
- 11 Rotate system timer switch **OFF**. **4**
- 12 Stow control pendant and secure compartment.
- 13 Secure any on-deck equipment.
- 14 Connect tow vehicle, secure coupler.
- 15 Connect safety chains, 12V cable, & break-away cable.
- 16 Retract tongue jack. **1**
- 17 Remove and store wheel chocks.
- 18 Verify signal light and brake operation.